


# Market dialogue - Railway Technique Contracts for new double track railway from Kleverud to Åkersvika

- KSÅ 6 – Railway systems Tracks and Catenary
- KSÅ 7 – Railway systems Electrical power and Telecom



# Agenda

- Presentation of the Participants
- Project Presentation
- Information about KSÅ-6 and KSÅ-7
- Input and questions from The Vendor
- Information about Minutes of Meeting and Publishing of Information regarding the contracts




# The Dovre Line: Kleverud-Sørli-Åkersvika

## Project summary

- 30 km new double track railway from Kleverud to Åkersvika
- The Hestnes tunnel 3,1 km
- Tangenvika railway bridge 1,07 km
- Substruction contracts
- Construction of new railway stations at Tangen and Stange
- Railway systems: Tracks, catenary, electro and telecom
- Designed for a max speed of 250 km/h

## Government funding

- Confirmed funding for Kleverud-Sørli 2020
- Planned funding for Sørli-Åkersvika 2022



# Contract KSÅ-6 and KSÅ-7 Railway technique



## Railway Technique:

KSÅ-6 Tracks and catenary, including cable ducts

KSÅ-7 Power supply 50Hz and Telecom

Civil works/substructure contracts:

- KS-1 The Hestnes tunnel
- KS-2 Tangenvika railway bridge
- KSÅ- 3 Furnesbakken-Stange
- SÅ-4 Stange-Åkersvika

# Presentation of The Projectmodell

- 3D drawings and model

# KSÅ-6 Railway systems and tracks/catenary

Description	Scope	Contract type and strategy	Contract notice*	Commencement*	Completion
<b>KSÅ-6</b> <b>Railway systems</b> <b>Tracks/Catenary</b>	<ul style="list-style-type: none"> <li>• Tracks/Catenary for 30 km railway</li> <li>• Track works               <ul style="list-style-type: none"> <li>- Ballasted tracks</li> <li>- 250 000 m3 ballast</li> <li>- Installation of company provided items:                   <ul style="list-style-type: none"> <li>- 65 000 m of Tracks</li> <li>- 100 000 Sleepers</li> <li>- 40 points</li> </ul> </li> </ul> </li> <li>• Catenary               <ul style="list-style-type: none"> <li>- Standard Bane NOR S25 overhead contact line system</li> <li>- Autotransformers</li> </ul> </li> <li>• Cable ducts</li> <li>• 500+ Million NOK</li> </ul>	<p>Engineering – Integrated team with Bane NOR employees and consulting engineers</p> <p>Contract basis: Construction contract: NS 8405</p>	<p>Medio 2023</p> <p>Negotiated procedure</p>	<p>Medio 2024</p>	<p>1.10.2027</p>

\*tentative timelines

# KSÅ-7 Railway systems and electrical power/telecom

Description	Scope	Contract type and strategy	Contract notice*	Commencement*	Completion
<b>KSÅ-7 Railway systems electrical power/telecom</b>	<ul style="list-style-type: none"> <li>• High voltage system               <ul style="list-style-type: none"> <li>- 22 kV 50 Hz</li> </ul> </li> <li>• Low Voltage system               <ul style="list-style-type: none"> <li>- 400 V 50 Hz</li> </ul> </li> <li>• Telecom system</li> <li>• CRM-system               <ul style="list-style-type: none"> <li>- Controlling-Regulation-Monitoring</li> </ul> </li> <li>• Installations includes (ca.):               <ul style="list-style-type: none"> <li>- 17 technical buildings</li> <li>- 2 Railway stations</li> <li>- 1 terminal of goods (timber)</li> <li>- 1 train tunnel</li> <li>- 8 antenna masts</li> <li>- All subsystems and components</li> </ul> </li> <li>• Installation of emergency systems in the Hestnes tunnel</li> <li>• Highvoltage cables, 22kV</li> <li>• Public information systems and video surveillance</li> </ul>	<p>Engineering – Integrated team with Bane NOR employees and consulting engineers</p> <p>Contract basis: Construction contract: NS 8405</p>	<p>Medio 2023</p> <p>Negotiated procedure</p>	Medio 2024	1.10.2027

\*tentative timelines, approximately 3 months after KSÅ-6

## Other relevant information


- The main contractor is to be certified within the quality system ISO 9001:2015 or with an equivalent system for accomplishment – system for the specifications, delivery's and responsibility connected with the contract
- Stringent demands connected to work and planning of scope of work in scheduled timelines for planned stops in the railway traffic in regards to qualifications, duration and quantity
- Bane NORs framework agreements can be transmitted to the contract
- KS-2 contract – The Tangenvika railway bridge has options connected to engineering and installation of slap track, this contract has not been signed yet, slap track solution is however not a part of the solution in the remaining contracts for this project
- The reconstruction of the station area at Hamar is not included in the scope of work for KSÅ-6 and 7
- KSÅ-5 engineering contract is signed with SWECO
- SÅ-24 –contract for preliminary works – announced on the marked medio September
- Frame agreement for Railway Technique – Area Midle-Norway –announced in July 2021
- Upcoming contracts will be announced here: <https://www.banenor.no/leverandor/anskaffelser/Anskaffelsesplaner/>
- Presentation and summary from the Market dialogue meetings will be announced at the project web page: <https://www.banenor.no/Prosjekter/prosjekter/dovrebanen/kleverud-sorli-akersvika/innhold/2021/markedsdialog-for-jernbanetekniske-entreprenorer-pa-ksa/>



Estimated time for building:  
Railway technique work (JBT) = blue

Work in scheduled timelines for planned  
stops in the railway traffic= red


# Plan of Execution for Railway technique work\*




\*tentative timelines

# Normal profile – interface between scope of work between substructure (red) and railway technique (green) on the track\*

ESPA - FURNESBAKKEN  
NORMALPROFIL FYLLING PÅ RETTLINJE  
JBT MARKERT GRØNT  
KS-2 MARKERT RØDT



# Normal profile – interface between scope of work between substructure (red) and railway technique (green) in The Tunnel



# Dialog and questions

Questions to The Vendor

Questions from The Vendor

